

DIGEST OF REVISIONS

2010 STANDARD PLANS ERRATUM NO. 18

July 15, 2016

GENERAL

For the 2010 edition Standards, Revised Standard Plans are new or revised standard plans. This was changed to be consistent with the definition for Revised Standard Specifications.

The listed Revised Standard Plans (RSPs) supersede the comparable standard plans in the 2010 edition Standard Plans book or supplement the 2010 edition Standard Plans book.

PLAN SPECIFIC

PLAN NO.	CHANGES
RSP A40C	New standard plan for edge line rumble strip.
RSP A40D	New standard plan for centerline rumble strip.
RSP A40E	New standard plan for rumble strip placement at freeway exit ramps, freeway entrance ramps, and intersections.
RSP A40F	New standard plan for rumble strip placement at intersections with left turn pockets, railroad crossings, private roads, and major driveways.
RSP A76BA	New standard plan for Type 60P concrete barrier.
RSP A76BB	New standard plan for Type 60PR concrete barrier.
RSP A76BC	New standard plan for Type 60AP concrete barrier.
RSP A84A	New standard plan for temporary desert tortoise fence.
RSP A84B	New standard plan for desert tortoise fence.
RSP A85	Revised tables and various notes with updated information.
RSP A85A	Added table for center post and removed "H" requirement from notes.
RSP A88A	Revised dome height and clarified Note 7.
RSP A88B	Clarified Note 4.
D72 (canceled)	Canceled this standard plan.
RSP D72A	New standard plan for Type OS, OL, and GOL CIP drainage inlets with LRFD upgrades.
RSP D72B	New standard plan for Type G1, G2, G3, G4, G5, and G6 CIP drainage inlets with LRFD upgrades.
RSP D72C	New standard plan for Type G1, G2, G3, G4, G5, and G6 CIP drainage inlets with LRFD upgrades.
RSP D72D	New standard plan for Type GT1, GT2, GT3, and GT4 CIP drainage inlets with LRFD upgrades.
RSP D72E	New standard plan for Type GO and GDO CIP drainage inlets with LRFD upgrades.
RSP D72F	New standard plan for CIP drainage inlet notes.
RSP D72G	New standard plan for CIP drainage inlet tables.
RSP D73 (canceled)	Canceled this standard plan.
RSP D73A	New standard plan for Type OS, OL, and GOL precast drainage inlets with LRFD upgrades.
RSP D73B	New standard plan for Type G1, G2, G3, G4, G5, and G6 precast drainage inlets with LRFD upgrades.
RSP D73C	New standard plan for Type G2 and G4 precast drainage inlets with LRFD upgrades.
RSP D73D	New standard plan for Type GT1, GT2, GT3, and GT4 precast drainage inlets with LRFD upgrades.
RSP D73E	New standard plan for Type GO and GDO precast drainage inlets with LRFD

DIGEST OF REVISIONS

2010 STANDARD PLANS ERRATUM NO. 18

	upgrades.
RSP D73F	New standard plan for precast drainage inlet notes.
RSP D73G	New standard plan for precast drainage inlet tables.
RSP D74	New standard plan for drainage inlet details.
D74A (canceled)	Canceled this standard plan.
RSP D74B (canceled)	Canceled this standard plan.
D74C (canceled)	Canceled this standard plan.
RSP D89	LRFD upgrades.
RSP D98D	New standard plan for slotted plastic pipe drain
RSP H2	Revised symbols to match cell library.
RSP H5	Revised detail titles.
RSP H6	Revised detail titles.
RSP H10	Clarified Note 3 and added cabinet positioning to Note 4.
RSP B7-11	Added Note 2 which used to be on this plan sheet in the 2006 edition, but removed in error in the 2010 edition.
RSP B11-51	Revised sidewalk width for ADA compliance. Removed electrolier details from Elevation detail and added Note 5 to reference ES-6A and ES-6B for electrolier mounting details. Added pedestal details.
RSP B11-54	Revised sidewalk width for ADA compliance. Added to Note 8 to reference B14-3 for minimum spacing between conduits and details at joints.
RSP B11-55	Revised Type 732B detail.
RSP B11-56	Revised Type 736B detail.
RSP B11-57	Revised Type 742B detail.
RSP B11-62	Revised sidewalk width for ADA compliance. Added to Note 4 to reference B14-3 for minimum spacing between conduits and details at joints.
RSP B11-66	Revised sidewalk width for ADA compliance. Added to Note 7 to reference B14-3 for minimum spacing between conduits and details at joints.
RSP B11-67	Revised sidewalk width for ADA compliance. Revised Section B-B.
RSP B11-71	New standard plan for California ST-20S bridge rail.
RSP B11-72	New standard plan for California ST-20S bridge rail.
RSP B11-73	New standard plan for California ST-20S bridge rail.
RSP B11-74	New standard plan for California ST-20S bridge rail.
RSP B11-75	New standard plan for California ST-70 bridge rail.
RSP B11-76	New standard plan for California ST-70 bridge rail.
RSP B11-77	New standard plan for California ST-70 bridge rail.
RSP B11-78	New standard plan for California ST-70 bridge rail.
RSP ES-3K	Corrected sheet title.
RSP ES-3L	Corrected sheet title.
RSP ES-6A	Revised base plate data and added CIDH pile foundation information.
RSP ES-6B	Revised mortar finish requirements in Detail N.
RSP ES-6C	Revised luminaire mast arm data and Notes 3 and 5.
RSP ES-6D	Revised pole and base plate data and added CIDH pile foundation information.
RSP ES-6E	Revised luminaire mast arm data and added pole data and CIDH pile foundation information.
RSP ES-6G	Revised Detail C and added pole and base plate data and CIDH pile foundation information.
RSP ES-7A	Revised elevation view of Detail B.
RSP ES-7B	Revised footing dimensions.
RSP ES-7C	Added Section B-B and Section C-C and revised pole and base plate data and CIDH pile foundation information.
RSP ES-7D	Added Section B-B and Section C-C and revised pole and base plate data and CIDH pile foundation information.
RSP ES-7E	Added Section B-B and Section C-C and revised pole and base plate data and CIDH pile foundation information.

DIGEST OF REVISIONS
2010 STANDARD PLANS ERRATUM NO. 18

RSP ES-7F	Added Section B-B and Section C-C and revised pole and base plate data and CIDH pile foundation information.
RSP ES-7G	Added Section B-B and Section C-C and revised pole and base plate data and CIDH pile foundation information.
RSP ES-7H	Added Section B-B and Section C-C and revised pole and base plate data and CIDH pile foundation information.
RSP ES-7J	Revised galvanizing drain hole information.
RSP ES-7M	Revised Detail A.
RSP ES-7N	Revised <i>CIDH Reinforcing and Inspection Tube Schedule</i> table and various details.
RSP ES-11	Revised Detail B-2.
RSP ES-16A	Revised Notes 4 and 5.
RSP ES-16B	Revised Notes 3, 4, and 5. Revised Elevation A and added Note 6.
RSP ES-16C	Revised pole and base plate data and CIDH pile foundation information.
RSP ES-16D	Revised pole and base plate data and CIDH pile foundation information. Removed Note 4, revised Notes 5, 6, and 8. Revised Elevation A and added corresponding note as new Note. 17.