

1-26-11

1. For MR  $\leq 2"$ , adjust reinforcement to clear sawcut for sealed joint. For MR  $> 2"$ , reinforcement must be normal to BB or EB and spaced to avoid joint seal assembly anchorage.
2. At the Contractor's option, approach slab transverse reinforcement may be placed parallel to BB or EB. Spacing of transverse reinforcement is measured along  $\ell$  roadway.
3. For details not shown, refer to Standard Plan B9-5.

**B9-4**